



## LAYOUT NOTES:

- All utilities shall be located and verified on site by the Contractor prior to construction.
   All supply and installation of labour and materials shall conform to the following as applicable at time
- of construction:
- of construction:

  Development Agreement (subdivision/phase)

  City of Sakatoon Standard Construction
  Specifications and Drawings: Parks Division in the
  edition that matches the date of the City approval of
  the Construction Drawings.

  All layout, including planting, paths, walls, formwork,
  rock work, furniture and equipment, shall be
  approved on site by the City prior to construction
  and installation. The City requires 24 hours
  notification prior to layout.

  Written dimensions take precedence over scaled
- Notinitiation prior to layout.

  Written dimensions take precedence over scaled dimensions. In case of discrepancy between listed quantities, symbols and labels on drawing(s), the symbols on drawing(s) shall be taken as correct.

  All dimensions are in metres unless otherwise
- noted.

  All conditions and dimensions shall be verified by the Contractor on site prior to commencement of
- the Contractor on site prior to commencement of work.

  7. All rocks/boulders are to be free of any spalling, cracks, crevices, or splinters. Selection shall be by the Designer/Contractor and approved by the City prior to placement.

  8. All furniture and equipment shall be installed per manufacturer's specifications and to current CSA standards. A letter of compliance to CSA guidelines shall be supplied prior to CCC.

  9. All trash receptacles shall be set back a minimum of 1.0m from the edge of all pathways.



DESIGNED BY: SBL

DRAWN BY: CHECKED BY: SBL

SCALE (24 X 36" Sheet): SCALE (11 X 17" Sheet): February 1, 2019

DATE:

Compound Layout Plan

Satellite Maintenance Yard Wilson Park

L-114A